### **Lecture 9 Special constructions**

1st Hour

2nd Hour

U-polder and Membrane polder
Surface level tunnels / New developments

Delft University of Technology, faculty of Civil Engineering

Dr. Ir. W. Broere and Ir. S. van der Woude

27 February 2009





1

**Department of Underground Space Technology** 

Delft University of Technology

## **Traditional Construction**

- River crossings
  - As short as possible
  - As confined as possible
- Sheet pile walls
- Underwater concrete floor
- Tension piles
- Objective
  - As cheap as possible

27/02/2009









#### The Dredging alternative

### Sand

### Step 1 : Dredging a deep channel



### Step 2 : Installation of impermeable membrane







### Step 3 : Partial refilling with sand



#### Step 4 : Lowering of the ground water table



### Step 5 : Construction of road and green slopes











## **Surface level tunnels** (special construction techniques / new devlopments)

- Tomas
- V-polder
- Supported membrane-polder
- U-polder
- Hollow dike
- Submerged tunnels
- Above ground tunnels



## New developments TOMAS







27 February 2009



## New developments V-polder





EINDSITUATIE

### New development —special techniques membrane- polder







Building phase: implementation sheet pile wall depends of location





EXECUTION PHASES



## New developments Special techniques U-polder





# New developments submerged tunnels



## New Developments Above ground tunnels





### **Case study Tramtunnel The Hague**

- Introduction project
- Top down and reduced hindrance for the surroundings
  - Diaphragm walls
- "Challenging" Design
  - Grout Arch
  - Gel injections
- What went wrong?
- How was it solved?
- Lessons learned
  - Based on evaluation report of Prof. van Tol

>>>construction method

- >>>construction method
- >>>construction method

27 February 2009



### **Tramtunnel, introduction project**



27 February 2009



### **Tramtunnel, introduction project**

- Length 1250m
- 2 stations ("Grote markt" and "Spui")
- Rail level -13,5m (surface level +2m)
- Opened in 2004
- Geology mainly sands and silts
- no reliable "impermeable" layer available
- Hindrance must be reduced to a minimum.
- >>> diaphragm walls (d-walls) (geology is suitable)
- >>> top down method

27 February 2009



### **Tramtunnel, introduction project**

• A tunnel for the Tram combined with parking space below surface in the inner city of The Hague. The busiest part in town.



### Tramtunnel, Top down D-walls



**T**UDelft

### Tramtunnel, Top down D-walls







## Tramtunnel, ir

Minimized hindrance does not mean No hindrance



27 February 2009

Tramtunnel,

Minimized hindrance does not mean No hindrance

27 February 2009

## Tramtunnel, "challenging" design

Cross-section Grote markt straat



- Conventional Contract with Design risk "owned" by client
- Grout Arch Functions:
  - Strut below excavation level>>>
    - Short and slim D-walls
  - Sealing layer?
  - Discussion between client and contractor on the risks



### Tramtunnel, "challenging design

### Cross-section Spui



- Gel layer Functions:
  - Additional sealing extra to the peat layer to prevent "breaking up of the peat layer. (Combined with draining of the sand below the peat)
















#### Inclination and analysis



41

**Delft University of Technology** 



#### diameter control



P Je Sc	'fahlnummer: 14–M– tlänge / Soll : 0.00 m tlänge / Ist : 2.83 m innedwinkel : 0 ° nlagennr. : 1											Datum Jetstart Jetdauer Jetvolumen Füllvolumen							Filter : 01.01.1980 - 08.08. : 07.08.1996 : 12:02:00 : 00:20:58 : 5.56 qbm : 0.00 qbm													
[		Vors	orschub			Drehzahl [II/min]					Jetdruck					1	Jetmenge					Fulldruck					Τ	Füllmenge				
	22	2 2	8	8		1	10/1	a B	40		100	200	300	400	500		50	100	1 200	E 260	300	AUL	100	00	400	500		2	100			
30 -																																
25 -						and a second sec																									D	
20 -																																
15 -	7				7										- 3																	
					}															and and												
10 -																																
						-																										

•Registration on the rig •Pulling velocity, •Rotation speed, •Torque, •Injection pressure, •Pump capacity of water jet and grout jet 43





#### •Control of return fluid





**Delft University of Technology** 

## Tramtunnel, Jet

## •Test columns real scale

27 February 2009



#### **Tramtunnel, Gel injection**



•Injection of chemicals that are injected via discrete injection openings.

 Injection in between the pores of the soil, this requires permeability



46

**Delft University of Technology** 

#### **Tramtunnel, Gel injection**

•Injection of chemicals that are injected via discrete injection openings.

27 February 2009



#### **Tramtunnel, Gel injection**

 Injection of chemicals that are injected via discrete injection openings.



27 February 2009

.



**Delft University of Technology** 









# Tramtunnel, Comparison jet grouting and gel injection

#### **Ground injection**

Low pressure 4 - 8 bar
Low capacity 4 - 8 ltr/minuut
Max. diameter 1,0 m
Flow through pores, no disturbance of the soil structure
Only possible in sand and gravel
Method: stacked spheres injected after each other

#### <u>Jetgrouting</u>

High pressure 300 - 500 bar
High pump capacity 125 - 300 ltr/min.
Max. diameter 1,3 m - 5,0 m
Cutting and partial replacement of soil structure
Possible in clay, silt and sands
Method: slowly pulling a rotating injection tool

•Gluing of sand grains

•Quick chemical reaction ca. 45 min.

•Mixing cement with soil

•Reaction cementation after ca. 30 min.





27 February 2009

# Tramtunnel, Comparison jet grouting and gel injection





**Delft University of Technology** 

#### Tramtunnel, What went wrong

- February 1998 almost at depth at the Kalvermarkt,
- Leakage of the grout arch >injection Belen dingen **Belendingen** >>Placing of ballast >>>Settlement beside pit ..... NAP >>>> filling of pit with water 0,7 m NAP Dak -1,2 m NAP -4,3 m NA -1 vloer -2 vloer 7,8 m NAP -13,0 m NAP  $\nabla$ -15.6 m NAP -16,9 mNAP Grouthoog

#### Tramtunnel, what went wrong

- For 2 years this was the situation
- Discussion between client and contractor:
  - Determining remaining risk
  - Developing a plan of action



27 February 2009

#### Tramtunnel, How was it solved?

Plan of Action:

- Opening of the contract >>> D&C contract (for grout arch parts)
- Design risk transferred to contractor (for grout arch parts)
- Excavation under air pressure
  - Increasing strength of floors and connection (where possible)
  - Placing of additional weight on top of the floor
  - Additional support structure on top of the floor
  - Additional anchors
  - PVE is reduced (consequence for the rail system)



#### Tramtunnel, How was it soled

#### Cross-section Grote markt straat



## **Tramtunnel, hyper barric works**



#### Tramtunnel, How was it soled



Cross-section Kalvermarkt

- Floor-2 already cast
- Extra support structure
- Increase stiffness of the d-wall required.

58



## **Tramtunnel, hyper barric works**



#### Tramtunnel, hyper barric works



## **Tramtunnel, Hyper barric works**







## **Tramtunnel, hyper barric works**



## Tramtunnel, hyper barric works



#### Tramtunnel, What went wrong part 2

- Problems solved
- Works were taken up in june 2000.
- Excavation was (re) started in Station Spui.
- leakage occurred directly adjacent to the section of the Kalvermarkt that was still filled with water.
- Leakage of the gel layer and peat layer
   >deformation of the intermediate wall
   >flooding of the station Spui



#### Tramtunnel, What went wrong part 2



- Why did this leakage occur?
  - The deep wells did not function anymore!
  - High hydraulic head over the peat layer
  - Failure of the peat layer >>leakage.



#### Tramtunnel, What went wrong part 2

Why did deep wells not function? "new" chemical phenomenon

- high pH in/around gel layer
- Organic matter dissolved
- Shallow surface >>lower pH
- Organic matter returns to solid
- Blocking the pores.

27 February 2009

• Slow process but substantial due to the 2 years of still stand



#### Tramtunnel, How was it solve

Plan of Action:

- Extensive repair works on the intermediate wall
- Account for risk of failure of the peat layer
- Account for the changed load case of the d-walls.
- Restart Excavation
  - Enormous extension of dewatering
    - New deep wells &
    - gravel piles.
  - Section wise excavation
  - Casting of a temporary floor
  - Anchoring of the temporary floor
  - Normal construction proceeds



#### YWS Geotechniek BY







#### VWS Geotechniek BV



#### YWS Geotechniek BY



27 February 2009


## Tramtunnel, What did we learn?

- 1. Injection layers built of columns (with jet grouting) and or injected spheres (gel injections) must be assumed to have defects.
- 2. Shallow injection layers with the purpose of sealing (close to the excavation level) should not be designed because of the risk off sand wells. Make sure that the covering layer has sufficient thickness and is drained properly.
- 3. Scientific research confirms that once a sand well occurs it quickly causes enormous movement of soil. Preventive measures must be taken within the hour.

27 February 2009



73

## Tramtunnel, What did we learn?

- 4. New pnenomenon (blocking of pores due to solution and precipitation of organic matter under changing pH)
- 5. <u>Underground construction</u> requires the following:
  - Robust design (which can take up some degree of failure or errors)
  - In the design one should account for defects in the soil and variation in soil parameters.
  - Make a failure analysis for individual construction parts.
  - Prepare preventive measures for possible failure or errors.
  - SWO: A design in which you thrust on specialized construction techniques requires that experience (risk assessment) is involved in the design.

